


Zap-Lok Connection System



Dia. (NPS): 2 to 12-inch (50-300mm)

Wall: Up to schedule 80

Material: Grade B through X65; SMLS, HFI or ERW

Service: Sweet and sour crude, gas or condensate, water

Pressure: As per line pipe material specification



Zap-Lok End-Preparation – Belling & Pinning

The first step is to prepare both ends of each pipe joint for the connection. One end of each joint (Bell End) is cold formed by expansion into a bell shape by the insertion of a hardened steel mandrel. A liquid lubricant is used to prevent galling of the steel pipe surface. The opposite end (Pin End) is grooved and has a slight bevel applied to the end by a tapered roller.


Belling Process cold forms standard API 5L pipe by approximately 5.2% creating a box end

<u>Pinning</u> Process creates a pre-formed beveled end




©Z014 NOV | Proprietary and confidential. Presentation N


Zap-Lok Installation Equipment



6-12 INCH NPS INSTALLATION PRESS



ALL-IN-ONE HPU



©2014 NOV | Proprietary and confidential.

Zap Lok installation 1: string pipe



Zap Lok installation 2: lift pipe into



Zap Lok installation 3: apply epoxy



Zap Lok installation 4: Align pipe



Zap Lok installation 5: Move Zap Lok machine in place



Zap Lok installation 6: make up joint with hydraulic press



Zap Lok installation 7: move machine to next joint





Zap-Lok Installation: Terrain









Zap-Lok Results: Less people on site

8 Inch welded construction (4 welding crews)

Welding Crew

1 Assistant Superintendent 1 Pickup and Trailer

1 Foreman – Craft 1 Sideboom Crane

1 Foreman – Labour 4 Welding Machines

1 Equipment Operators 3 Tracked Utility Vehicles

8 Skilled Labourers

4 Welders + 4 Welders Helpers

Field Joint Coating Crew

1 Foreman – Craft 2 light duty pickups

4 Skilled Labor 1 utility trailer

1 generator

1 abrasive blasting unit

X Ray Crew

1 Ray Technician X Ray processing truck

1 Assistant

Total people on site for Total pi

construction: 27 people

Total pieces of equipment

on site:

16 pieces

8 Inch Zap Lok construction (1 Zap-Lok crew0

Zap Lok installation crew

3 Laborers 1 Pickup

2 Sideboom operators 2 Sideboom Cranes

1 Supervisor / Permit Holder 1 Zap-Lok Press

1 Zap-Lok Operator 1 Zap Lok Power Unit

Total people on site for construction:

Total pieces of equipment on site:

7 people 5 pieces

©2014 NOV | Proprietary and confidential. Presentation Name - 00/00/00

Zap-Lok Results: Less people on site

Actual installation times for lines in Eagle Ford (4 x welding spreads vs. 1 x Zap-Lok spread)					
Line Section	Pipeline diameter	Pipeline length	Total days of construction	Average installation Pipe Per Day	
D16 Line B	8 inch	9,280 m	8	1.16 km	
A12 Line B	8 inch	18,952 m	15	1.26 km	
Transfer Line B	8 inch	9,978 m	7	1.43 km	
D2 Line B	12 inch	7,242 m	11	0.66 km	
D16 Line C	12 inch	9,283 m	8	1.16 km	
C4 – Zap-Lok	8 inch	18, 227 m	7	2.60 km	

Installation Method	Ave	Average installation speed		
Welded 8 inch pipeline – 4 x welding spreads	1.28km / day	or	320 meters /day / spread	
Zap Lok 8 inch pipeline – 1 x Zap-Lok spread	2.60km / day	or	2,600 meters /day / spread	

©2014 NOV | Proprietary and confidential. Presentation Name - 00/00/00 | 17

THANK YOU

Tarun Maggo Manager (PNG-Steel) IndraPrastha Gas Ltd. 9650926622 Tarun@igl.co.in